

28G METAL ROOFING AG PANEL (COLOR TBD)
PURLINS 2X4 SPF #2 OR BETTER FASTENED LAYING FLAT
SYNTHETIC ROOFING FELT

ALUMINUM FASCIA COVER
SUBFASCIA 2X6 SPF #2 & BETTER
VENT 12" SOFFIT ON EAVE
H2.5 HURRICANE TIES

2X12 SYP(2) #1 TRUSS CARRIER
GRK RSS STRUCTURAL SCREWS

28G METAL SIDING AG PANEL
(COLOR TBD)
VAPOR BARRIER (HOUSEWRAP)
2X4 PURLINS @24" O.C.

3PLY LAMINATED POST WITH #2.40ACQ TREATED GC BOTTOM
MAX SPACING OF 8' O.C.

(2) 2X8 TG TREATED SKIRT BOARD

4" CONCRETE SLAB W/ STRUCTURAL STRENGHT 3500 PSI
UNDISTURBED SOIL OR COMPACTED GRAVEL

BACKFILL 24" HOLE WITH SAND/GRAVEL FILL & COMPACT

PIER FOOTING 5000 PSI 18"X9" THICK CONCRETE PAD

POST CLEATS GC 2X6 ON EACH SIDE OF POST STARTING
6" ABOVE PIER FOOTING

1-3/4"X14" LVL

LAMINATED POST
NOTCHED

2PLY 1 3/4"X14" LVL
2X6 SPF

OVERHEAD DOOR HEADER
DETAIL 3/4" = 1'0"

PROPOSED LAYOUT
1/8" = 1'0"

TYP CROSS SECTION
1/2" = 1'0"

Elevation 5

POST LAYOUT
3/16" = 1'0"

NO.	DESCRIPTION	BY	DATE

PROPOSED STORAGE
BUILDING

GENOA BAPTIST CHURCH
7562 LEWIS CENTER ROAD
DELAWARE OH 43082

BY: SCHWARTZ QUALITY CONSTRUCTION

12/02/24

SHEET:

3